



NOTES:

1. All pipes and post sizes are nominal diameter (N.D.).
2. Gate frame shall be of welded pipe construction. All welding shall conform to the Specifications of the American Welding Society "Structural Welding Code".
3. For all welded connections: corners shall be mitered and all pipe braces properly coped.
4. All welded connections shall be painted with two coats of Z.R.C. cold galvanizing compound.
5. Gate hinges shall be tack welded to gate posts and frames.
6. Chain link fabric, pipes, fittings, fasteners, truss rod, posts and hog rings shall be hot-dip galvanized.
7. Wire fastenings shall be No. 12 gauge galvanized tie wire.
8. Chain link fabric shall be continuous and fastened to side frame pipes by tension bars with tension bands evenly spaced at 15" o.c. (max.).
9. Chain link fabric shall be fastened to top and bottom frame pipes with wire fastenings evenly spaced at 12" o.c. (max.).
10. Chain link fabric shall be fastened to truss rods with No. 9 gauge hog rings evenly spaced at 12" o.c. (max.).
11. Top and bottom selvages of chain link fabric shall be knuckled.
12. All wire fastenings shall be wrapped around chain link a minimum of two complete turn. (Hooking of wire ends shall not be permitted).
13. After installation, all bolt ends shall be cut flush with the nuts and ground smooth.

F-9(F)

CITY COUNTY OF HONOLULU

4'-0" GATE DETAIL (7'-0" HIGH)

SCALE: NOT TO SCALE

REVISED: FEBRUARY 2007

STANDARD
DETAILS

F-9